








standard

CONDENSATE REMOVAL PUMP

peristaltic sets the standard for reliability. The remote install





6.5L/h max. flow



12m max. head (flow rate 6.5L/h)


KEY FEATURES


- AC cooling signal operated
- Remote install possible
- Pumps contaminated water
- Can run dry












STANDARD SPECIFICATIONS		
Max. flow	6.5L/h @ 12m head	
Max. head	12m	
Max. suction lift	3m	
Sound level@1m	47dB(A)	
Power supply	230 VAC, 0.2A, 50-60Hz	
Rated	Continuously	
Class	I appliance	
Max. unit output	8.5kW / 29,000Btu/h	
Max. water temp	40°C / 104°F	
Inlet/outlet	6mm ID	
IP Protection	IP21	
Safety switch	n/a	
Thermal protection	✓	
Fully potted	n/a	



STANDARD OPTIONS		
Standard		FP2081/2

SUGGESTED XTRA ACCESSORIES			
Description		Part No.	
Peri Spare Tube Kit		FP1282	
1 Amp Fuse		FP2620	
Tube To Soil Stack Adaptor		FP2038	



For more installation accessories take a look at our Aspen Xtra range

IN THE BOX

Standard pump • 2m Plug & play power cable

- Wall mounted bracket Fixing kit
- Install manual
- Download manual at aspenpumps.com
- View install video at aspenpumps.com













Self priming